

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 3 of 16

Amendments to the Claims

This listing of claims will replace all prior versions, and listings, of claims in the application:

Listing of Claims:

1. (Currently Amended) A method for providing fault tolerance in a VLAN having a topology defined by a spanning tree having a root node and at least one leaf node, the root and leaf nodes interconnected by connections in a connection-based network, the method comprising:
 - sending from a first node in a connection used by the VLAN, in a leaf-to-root direction a series of continuity checking packets;
 - detecting the continuity checking packets at a second node in the connection wherein the second node is the root node or is located between the first node and the root node, the connection passing through at least one intermediate node between the first and second nodes; and,
 - generating a request for a change in the topology of the VLAN in response to not receiving one or more continuity checking packets at the second node.
2. (Original) The method of claim 1 comprising generating a connection rerouting request in response to the request for a change in the topology of the VLAN.
3. (Original) The method of claim 1 wherein generating a request for a change in the topology of the VLAN comprises generating a topology change notification.

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 4 of 16

4. (Original) The method of claim 1 wherein the first node is at a leaf of the spanning tree.
5. (Original) The method of claim 4 wherein the second node is at a root of the spanning tree.
6. (Original) The method of claim 1 wherein the connection-based network comprises an ATM network and sending a series of continuity checking packets comprises sending a series of OAM cells.
7. (Canceled)
8. (Currently Amended) ~~The method of claim 7~~ A method for providing fault tolerance in a VLAN having a topology defined by a spanning tree having a root node and at least one leaf node, the root and leaf nodes interconnected by connections in a connection-based network, the method comprising:
sending from a first node in a connection used by the VLAN, in a leaf-to-root direction a series of continuity checking packets;
detecting the continuity checking packets at a second node in the connection wherein the second node is the root node or is located between the first node and the root node; and,
generating a request for a change in the topology of the VLAN in response to not receiving one or more continuity checking packets at the second node
wherein the connection-based network comprises an ATM network, and sending a series of continuity checking packets comprises sending a series of OAM cells at intervals are in the range of ½ second to 2 seconds.

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 5 of 16

9. (Original) The method of claim 1 comprising monitoring a time elapsed since receipt of a continuity checking packet at the second node and generating the request for a change in the topology of the VLAN if the time elapsed exceeds a threshold.
10. (Original) The method of claim 1 comprising monitoring a number of continuity checking packets received at the second node within a time window and generating the request for a change in the topology of the VLAN if the number of continuity checking packets received at the second node is less than a threshold number.
11. (Original) The method of claim 1 also comprising sending continuity checking packets from the root node to one or more leaf nodes of the spanning tree and detecting the continuity checking packets at the one or more leaf nodes of the spanning tree.
12. (Currently Amended) A method for providing fault tolerance in an ethernet VLAN comprising a plurality of ethernet segments connected to an ATM network by bridges and an ATM virtual circuit extending between a first one of the bridges and a second one of the bridges, the method comprising:
 - configuring nodes at first and second ends of the virtual circuit respectively to source and sink OAM continuity checking cells;
 - sending from a source port at the first end of the virtual circuit OAM continuity checking cells at a specified rate of at least one OAM continuity checking cell per 2 seconds;
 - receiving the OAM continuity checking cells at a sink port at the second end of the virtual circuit; and,

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 6 of 16

generating a request for a change in the topology of the VLAN in response to the sink port determining that it has not received a number of the OAM continuity checking cells.

13. (Original) The method of claim 12 comprising generating a signal to trigger a soft permanent virtual circuit reroute in response to the request for a change in the topology of the VLAN.
14. (Original) The method of claim 12 wherein generating a request for a change in the topology of the VLAN comprises generating a spanning tree protocol topology change notification.
15. (Original) The method of claim 14 wherein generating a request for a change in the topology of the VLAN comprises sending a BPDU to a node of the VLAN.
16. (Original) The method of claim 14 wherein generating a request for a change in the topology of the VLAN comprises sending a BPDU to a root node of the VLAN.
17. (Original) The method of claim 12 wherein the sink port is at a root node of the VLAN, the source port is at a leaf node of the VLAN and the OAM continuity checking cells travel over the connection in a leaf-to-root direction.
18. (Original) The method of claim 12 wherein the VLAN comprises a plurality of segments interconnected in a topology defined by a spanning tree protocol having a root at the second end of the virtual circuit and a leaf at the first end of the virtual circuit.

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 7 of 16

19. (Original) The method of claim 12 comprising determining that the sink port has not received a predetermined number of the OAM continuity checking cells by determining that a time elapsed since receipt of a most recently received one of the OAM continuity checking cells exceeds a threshold time.
20. (Currently Amended) A method for rerouting a connection in a connection-based network, the connection carrying data traffic between ethernet segments of a VLAN, the method comprising:
- configuring nodes at first and second ends of the connection respectively to source and sink continuity checking packets;
 - sending continuity checking packets at a specified rate from the node at the first end of the connection;
 - allowing the continuity checking packets to pass along the connection through at least one intermediate node between the node at the first end of the connection and the node at the second end of the connection;
 - receiving the continuity checking packets at a packet sink at the node at the second end of the connection;
 - generating a request for a change in the topology of the VLAN in response to the packet sink not receiving a predetermined number of the continuity checking packets;
 - generating a reroute signal for the connection in response to the request for a change in the topology of the VLAN; and,
 - rerouting the connection through the connection-based network in response to the reroute signal.

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 8 of 16

21. (Original) The method of claim 20 wherein the connection-based network comprises an ATM network and the continuity checking packets comprise OAM cells.
22. (Original) The method of claim 20 wherein the VLAN comprises a plurality of segments interconnected in a topology defined by a spanning tree protocol having a root at the second end of the connection and a leaf at the first end of the connection.
23. (Currently Amended) The method of claim ~~22~~ 21 comprising determining that the cell sink has not received a predetermined number of the OAM cells by determining that a time elapsed since receipt of a most recently received one of the OAM cells exceeds a threshold time.
24. (Original) The method of claim 23 wherein the connection comprises a soft permanent virtual circuit and the reroute signal comprises a VC reroute signal.
25. (Currently Amended) A virtual LAN having a topology comprising a spanning tree, the virtual LAN comprising:
 - a plurality of network segments each bridged to a ~~connection-oriented~~ connection-based network;
 - a plurality of connections in the connection-based network, the connections interconnecting the plurality of network segments;
 - a packet source located on a first one of the connections, the packet source configured to generate and send on the connection temporally spaced apart continuity checking packets in a direction toward a root of the spanning tree;
 - a packet sink located on the first one of the connections at a location between the packet source and the root of the spanning tree, the packet sink configured

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 9 of 16

to receive the continuity checking packets and to generate a request for a change in the topology of the VLAN in response to not receiving one or more of the continuity checking packets sent by the packet source wherein the connection-based network comprises at least one intermediate node located along the connection between the packet source and the packet sink.

26. (Canceled).
27. (Currently Amended) The virtual LAN of claim ~~26~~ 25 wherein the connection-based network comprises an ATM network.
28. (Original) The virtual LAN of claim 27 wherein the packet source is configured to generate and send OAM cells and the packet sink is configured to receive the OAM cells.
29. (Currently Amended) The virtual LAN of claim ~~26~~ 28 wherein the packet source is associated with a timer and the packet source is configured to generate and send the OAM cells at equally spaced-apart times.
30. (Original) The virtual LAN of claim 29 wherein the packet sink is associated with a timer and the packet sink is configured to generate the request for a change in the topology of the VLAN when a time longer than a threshold time has passed since the packet sink has received one of the OAM cells.
31. (Original) The virtual LAN of claim 26 comprising, on each of a plurality of the connections:
a packet source configured to generate and send continuity checking packets at intervals to a corresponding packet sink located on the one of the

Application No. 10/026713
Amendment dated 17 January 2006
Reply to Office Action of 20 September 2005

Page 10 of 16

- plurality of the connections at a location between the packet source and the root of the spanning tree, the packet sink configured to receive the continuity checking packets and generate the request for a change in the topology of the VLAN in response to determining that a number of the continuity checking packets sent by the corresponding packet source have not been received.
32. (Original) The virtual LAN of claim 31 wherein the spanning tree comprises a plurality of leaves and one of the packet sources is located at each of the leaves of the spanning tree.
33. (Original) The virtual LAN of claim 32 wherein packet sinks corresponding to the packets sources located at the leaves of the spanning tree are located at the root of the spanning tree.
34. (Original) The virtual LAN of claim 33 comprising a VLAN-level fault tolerance mechanism wherein the packet sink is configured to trigger the VLAN-level fault tolerance mechanism in response to not receiving one or more of the continuity checking packets sent by the packet source.
35. (Original) The virtual LAN of claim 33 wherein the root of the spanning tree is located at a bridge and the bridge generates and sends bridge protocol data units to other bridges located at the leaves of the spanning tree.
36. (Currently Amended) A method for providing fault tolerance in a VLAN having a topology, the VLAN comprising a plurality of segments interconnected by connections in an ATM network the method comprising:

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 11 of 16

at a cell source on one of the connections
generating a series of continuity checking cells;
at a cell sink on the one of the connections
receiving the continuity checking cells;
between generating the continuity checking cells and
receiving the continuity checking cells, allowing the
continuity checking cells to pass along the one of the
connections through at least one intermediate node on the
one of the connections, the intermediate node between the
cell source and the cell sink;
determining that a number of the continuity checking
cells sent by the cell source have not been received at
the cell sink;
generating a fault indication in response to
determining that a number of the continuity checking
cells have not been received at the cell sink, and,
triggering a change in the topology of the VLAN in
response to the fault indication.

37. (New) The method of claim 8 comprising generating a connection rerouting request in response to the request for a change in the topology of the VLAN.
38. (New) The method of claim 8 wherein generating a request for a change in the topology of the VLAN comprises generating a topology change notification.
39. (New) The method of claim 8 wherein the first node is at a leaf of the spanning tree.
40. (New) The method of claim 39 wherein the second node is at a root of the spanning tree.
41. (New) The method of claim 8 comprising monitoring a time elapsed since receipt of a continuity checking packet at

Application No. 10/026713
Amendment dated 12 January 2006
Reply to Office Action of 20 September 2005

Page 12 of 16

the second node and generating the request for a change in the topology of the VLAN if the time elapsed exceeds a threshold.

42. (New) The method of claim 8 comprising monitoring a number of continuity checking packets received at the second node within a time window and generating the request for a change in the topology of the VLAN if the number of continuity checking packets received at the second node is less than a threshold number.